



Simplifying Trade Processes for Kenya's Competitiveness

KENYA TRADE NETWORK AGENCY (KENTRADE)

Embankment Plaza – First Floor P.O. Box 36943-00200-NAIROBI

Tel: +254 020 2614896; email: info@kentrade.go.ke ;

procurement@kentrade.go.ke

ADDENDUM No 2

TENDER NO. KTNA/OT/10/2020-2021

THE PROPOSED OFFICE RE-DESIGN OF EXISTING OFFICE SPACE INCLUDING PARTITIONING AND REFURBISHMENT WORKS AT GROUND AND 1ST FLOORS, EMBANKMENT PLAZA – NAIROBI.

NO	DESCRIPTION
I	This is to share The Bills of Quantity that were inadvertently left out in the Tender Invitation Published on our Website and the PPIP Portal.

The addendum & clarification form part of the bidding document and is binding on all bidders. All other terms and conditions of the tender remain the same.

CHIEF EXECUTIVE OFFICER

BILLS OF QUANTITIES

PARTICULAR PRELIMINARIES

ITEM	DESCRIPTION	K.SHS
	<u>PARTICULAR PRELIMINARIES</u> A PRICING ITEMS OF PRELIMINARIES Prices SHALL BE INSERTED against items of “preliminaries” in the tenderer’s priced Bills of Quantities. The contractor is advised to read and understand all preliminary items. B DESCRIPTION OF THE WORKS The PROPOSED works to be carried out under this contract involves; office re-design for partitioning to create new office space; refurbishment of existing offices; floor finishes; doors and venetian window blinds; including associated electrical installations and structured cabling works as Proposed Office Re-design of Existing Office Space including Partitioning and Refurbishment Works at Ground and 1st Floor, Embankment Plaza - Nairobi C MEASUREMENTS In the event of any discrepancies arising between the Bills of Quantities and the actual works, the site measurements shall generally take precedence. However, such discrepancies between any contract documents shall immediately be referred to the PROJECT MANAGER in accordance with Clause 22 of the Conditions of Contract. The discrepancies shall then be treated as a variation and be dealt with in accordance with Clause 22 of the D LOCATION OF SITE The site of the proposed works is located at Embankment Plaza - Nairobi. The Contractor is advised to visit the site, to familiarize with the nature and position of the site. No claims arising from the Contractor’s failure to do so will be entertained. E SIGNING OF THE TENDER DOCUMENTS The bidder shall append his / her signature and / or company ‘s rubberstamp on the tender document.	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	K.SHS
A	DEMOLITIONS AND ALTERATIONS The Contractor is to allow for all temporary protection required during the works including ordinary and special dust screens, hoardings, barriers, warning signs, etc as directed by the Project Manager and as necessary for the adequate propping and protection of existing property, finishes, workmen employed on the site, employer's agents and the public. Any damage or loss incurred due to the insufficiency of such protection must be made good by the Contractor. All protective devices are to be removed on completion of the works and any necessary making good consequent upon this is to be executed to the satisfaction of the Project Manager The works shall be propped, strutted and supported as necessary before any alteration or demolition work commences. Prices shall include for all cleaning and preparatory work to structure and finishes and for making good to all finishes on completion whether or not specifically described. Unless described as set aside for re-use all arising debris and surplus materials shall be carefully removed from building and carted away from site. The Contractor shall be entirely responsible for any breakage or damage which may occur to materials required for re-use during their removal unless it is certified by the Project Manager that such damage or breakage was inevitable as a result of the condition of the item concerned B CLEARING AWAY The Contractor shall remove all temporary works, rubbish, debris and surplus materials from the site as they accumulate and upon completion of the works, remove and clear away all plant, equipment, rubbish, unused materials and stains and leave in a clean and tidy state to the reasonable satisfaction of the Project Manager. The whole of the works shall be delivered up clean, complete and in perfect condition in every respect to the satisfaction of the Project Manager. C CLAIMS It shall be a condition of this contract that upon it becoming reasonably apparent to the Contractor that he has incurred losses and / or expenses due to any of the contract conditions, or by any other reason whatsoever, he shall present such a claim or intent to claim notice to the PROJECT MANAGER within the contract period. No claim shall be entertained upon the expiry of the said contract period.	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	K.SHS
A	PAYMENTS The tenderer's attention is drawn to the fact that the GOVERNMENT DOES NOT MAKE ADVANCE PAYMENTS but pays for work done and materials delivered to sit: all in accordance with Clause 23 of the Conditions of Contract Agreement. In order to facilitate this, a list of the general component elements for the works is given at the summary page of these specifications and the tenderer is requested to break down his tender sum commensurate to the said elements B PREVENTION OF ACCIDENT, DAMAGE OR LOSS The Contractor is notified that these works are to be carried out on a restricted site where the client is going on with other normal activities. The Contractor is thus instructed to take reasonable care in the execution of the works as to prevent accidents, damage or loss and disruption of activities being carried out by the Client. The Contractor shall allow in his rates any expense he deemed necessary by taking such care within the site. C WORKING CONDITIONS The Contractor shall allow in his rates for any interference that he may encounter in the course of the works for the Client may in some cases ask the Contractor not to proceed with the works until some activities within the site are completed, as the facility will be operating as usual during the course of the contract. D SIGNBOARD Allow for providing, erecting, maintaining throughout the course of the Contract and afterwards clearing away a signboard as designed, specified and approved by the Project Manager. E LABOUR CAMPS The Contractor shall not be allowed to house labour on site. Allow for transporting workers to and from the site during the tenure of the contract. F MATERIALS FROM DEMOLITIONS Any materials arising from demolitions and not re-used shall become the property of the Employer. The Contractor shall allow in his rates the cost of transporting the demolished materials to the Employer,	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	K.SHS
A B C D E F	PRICING RATES The tenderer shall include for all costs in executing the whole of the works, including transport, replacing damaged items, fixing, all to comply with the said Conditions of Contract. SECURITY The Contractor shall allow for providing adequate security for the works and the workers in the course of execution of this contract. No claim will be entertained from the Contractor for not maintaining adequate security for both the works and workers. URGENCY OF THE WORKS The Contractor is notified that these “ works are urgent” and should be completed within the period stated in these Particular Preliminaries. The Contractor shall allow in his rates for any costs he/ she deems that he/she may incur by having to complete these works within the stipulated contract period. PAYMENT FOR MATERIALS ON SITE All materials for incorporation in the works must be stored on site before payment is effected, unless specifically exempted by the Project Manager. This is to include materials of the Contractor, nominated sub-Contractors and nominated suppliers. EXISTING SERVICES Prior to the commencement of any work, the Contractor is to ascertain from the relevant authority the exact position, depth and level of all existing services in the area and he/she shall make whatever provisions may be required by the authorities concerned for the support, maintenance and protection of such services. BID SECURITY The Bidder shall furnish, as part of his bid, a security as specified in the tender advertisement. The bid security shall, at the bidder’s option, be in the form of a certified cheque, bank draft, standby letter of credit or guarantee from a reputable bank located in Kenya or foreign bank which has been determined by the bidder to be acceptable to the Government. The format of the bank guarantee shall be in accordance with the sample forms of bid security included in the post qualification forms, other formats may be permitted, subject to the prior approval of the Government. Letters of credit, bank Guarantees issued as surety for the bid shall be valid for a period of One Hundred and Fifty (150) days from the date of Tender Opening.	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	K.SHS
A PERFORMANCE BOND A bond of 5% of the contract sum will be required in accordance with clause 6.00 (as amended) on award of contract of the Instructions to Tenderer's. No payment on account for the works executed will be made to the contractor until he has submitted the Performance Bond to the Project Manager duly signed, sealed and stamped from an approved Bank. B TENDER DOCUMENTS Tender documents are as listed in Clause 2.1 of the Instruction to Tenderer's Page STD/8 A DELIVERY OF TENDER Tenders and all documents in connection therewith, as specified above must be delivered in the addressed envelope which should be properly sealed and deposited at the offices as specified in the letter accompanying these documents or as indicated in the advertisement. Tenders will be opened at the time specified in the letter accompanying these Tender Documents or as indicated in the advertisement. Tenders delivered/received later than the above time will not be opened. C VALUE ADDED TAX The Contractor's attention is drawn to the Legal Notice in the Finance Act part 3 Section 21(b) operative from 1st September, 1993 which requires payment of VAT on all contracts. The Contractor should therefore include allowance in his rates and prices for prices for VAT and any other Government taxes currently in force. The tenderer is advised that in accordance with Government public notice No. 35 & 36 Dated 11th September 2003 operational from 1st October 2003, VAT will be deducted against the contract sum at the prevailing rate by the Employer and remitted directly to the Commissioner of VAT through all interim certificates. It should however be noted that this is not additional tax but a new mode of payment for VAT, any excess payment will be refundable once the Contractor has submitted monthly returns to the Commissioner of VAT who will do the refunds when satisfied that the VAT regulations have been complied with. NB: VAT SHALL be added at the Grand summary page (GS/1)		
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	K.SHS
A	<u>PARTICULARS OF INSERTIONS TO BE MADE IN APPENDIX TO CONTRACT AGREEMENT</u>	
	The following are the insertions to be made in the appendix to the Contract Agreement: -	
	Period of Final Measurement 3 Months From Practical completion	
	Defects Liability Period 6 Months from Practical completion	
	Date for Possession To be agreed with the Project Manager	
	Date for Completion ...8... Weeks from date of Possession	
	Liquidated and Ascertained At the rate of Kshs.. 35,000 ... per week or part thereof	
	Prime cost sums for which	
	The Contractor desires to tender	
	Period of Interim Certificates Monthly	
	Period of Honouring Certificates 30 days	
	Percentage of Certified Value Retained 10%	
	Limit of Retention Fund 5%	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	K.SHS
	<u>COLLECTION</u> Brought forward from page PP/1 Brought forward from page PP/2 Brought forward from page PP/3 Brought forward from page PP/4 Brought forward from page PP/5 Brought forward from page PP/6 Brought forward from page PP/7	
	TOTAL FOR PARTICULAR PRELIMINARIES CARRIED TO SUMMARY OF PRELIMINARIES	

GENERAL PRELIMINARIES

ITEM	DESCRIPTION	
	GENERAL PRELIMINARIES A. PRICING ITEMS OF PRELIMINARIES AND PREAMBLES Prices will be inserted against items of Preliminaries in the Contractor's priced Bills of Quantities and Specification. The Contractor shall be deemed to have included in his prices or rates for the various items in the Bills of Quantities or Specification for all costs involved in complying with all the requirements for the proper execution of the whole of the works in the Contract. B. ABBREVIATIONS Throughout these Bills, units of measurement and terms are abbreviated and shall be all the requirements for the proper execution of the whole of the works in the Contract. <i>C.M.</i> Shall mean cubic metre <i>S.M.</i> Shall mean square metre <i>L.M.</i> Shall mean linear metre <i>MM</i> Shall mean Millimetre <i>Kg.</i> Shall mean Kilogramme <i>No.</i> Shall mean Number <i>Prs.</i> Shall mean Pairs <i>B.S.</i> - Shall mean the British Standard Specification Published by the British Standards Institution, 2 Park Street, London W.I., England. <i>Ditto</i> - Shall mean the whole of the preceding description except as qualified in the description in which it occurs. <i>m.s.</i> Shall mean measured separately. <i>a.b.d</i> Shall mean as before described.	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	
A.	EXCEPTION TO THE STANDARD METHOD OF MEASUREMENT <i>Attendance</i> ; Clause B19(a) of the Standard Method of Measurement is deleted and the following clause is substituted:- Attendance on nominated Sub-Contractors shall be given as an item in each case shall be deemed to include: allowing use of standing scaffolding, mess rooms, sanitary accommodation and welfare facilities; provision of special scaffolding where necessary; providing space for office accommodation and for storage of plant and materials; providing light and water for their work: clearing away rubbish; unloading checking and hoisting: providing electric power and removing and replacing duct covers, pipe casings and the like necessary for the execution and testing of Sub- Contractors' work and being responsible for the accuracy of the same. <i>Fix Only</i>:- "Fix Only" shall mean take delivery at nearest railway station (Unless otherwise stated),pay all demurrage charges, load and transport to site where necessary, unload, store,unpack, assemble as necessary, distribute to position, hoist and fix only. B. EMPLOYER The "Employer" is: The Chief Executive Officer, Kenya Trade Network Agency (KENTRADE) The term "Employer" and "Government" wherever used in the contract document shall be synonymous C. PROJECT MANAGER The term "P.M." wherever used in these Bills of Quantities shall be deemed to imply the Project Manager as defined in Condition 1 of the Conditions of Contract or such person or persons as may be duly authorised to represent him on behalf of the Government. D. ARCHITECT The term "Architect" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is Regional Works Officer, Nairobi Region - State Department of Public Works, P.O. Box 42267, NAIROBI.	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	
A	QUANTITY SURVEYOR The term "Quantity Surveyor" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is Regional Works Officer, Nairobi Region - State Department of Public Works, P.O. Box 42267, NAIROBI.	
B	ELECTRICAL ENGINEER The term "Electrical Engineer" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is Regional Works Officer, Nairobi Region - State Department of Public Works, P.O. Box 42267, NAIROBI.	
C	MECHANICAL ENGINEER The term "Mechanical Engineer" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is Regional Works Officer, Nairobi Region - State Department of Public Works, P.O. Box 42267, NAIROBI.	
D	STRUCTURAL ENGINEER The term "Structural Engineer" shall be deemed to mean "The P.M." as defined above whose address unless otherwise notified is Regional Works Officer, Nairobi Region - State Department of Public Works, P.O. Box 42267, NAIROBI.	
E	FORM OF CONTRACT The Form of Contract shall be as stipulated in the Republic of Kenya's Standard Tender Document for Procurement of Building Works(2000 Edition) included herein The Conditions of Contract are also included herein <i>Conditions of Contract</i> These are numbered from 1 to 37 as set out in pages 18 to 38 of these tender documents. Particulars of insertions to be made in the Appendix to the Contract Agreement will be found in the Particular Preliminaries part of these Bills of Quantities	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	
A BOND. The Contractor shall find and submit on the Form of Tender an approved bank who will be willing to be bound to the Government in an amount equal to five per cent (5) of the Contract amount for the due performances of the Contract up to the date of completion as certified by the PROJECT MANAGER and who will, when and if called upon, sign a Bond to that effect on the relevant standard form included herein. (without the addition of any limitations) on the same day as the Contract Agreement is signed, by the Government, the Contractor shall furnish within seven days another Surety to the approval of the Government. B PLANT, TOOLS AND VEHICLES Allow for providing all scaffolding, plant, tools and vehicles required for the works except in so far as may be stated otherwise herein and except for such items specifically and only required for the use of nominated Sub-Contractors as described herein. No timber used for scaffolding, formwork or temporary works of any kind shall be used afterwards in the permanent work. C TRANSPORT. Allow for transport of workmen, materials, etc., to and from the site at such hours and by such routes as may be permitted by the competent authorities. D MATERIALS AND WORKMANSHIP. All materials and workmanship used in the execution of the work shall be of the best quality and description unless otherwise stated. The Contractor shall order all materials to be obtained from overseas immediately after the Contract is signed and shall also ensure they are onsite when required for use in the works. The Bills of Quantities shall not be used for the purpose of ordering materials. E SIGN FOR MATERIALS SUPPLIED. The Contractor will be required to sign a receipt for all articles and materials supplied by the PROJECT MANAGER at the time of taking deliver thereof, as having received them in good order and condition, and will thereafter be responsible for any loss or damage and for replacements of any such loss or damage with articles and/or materials which will be supplied by the PROJECT MANAGER at the current market prices including Customs Duty and V.A.T., all at the Contractor's own cost and expense, to the satisfaction of the PROJECT MANAGER		
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	
A B C	STORAGE OF MATERIALS The Contractor shall provide at his own risk and cost where directed on the site weather proof lock-up sheds and make good damaged or disturbed surfaces upon completion to the satisfaction of the PROJECT MANAGER Nominated Sub-Contractors are to be made liable for the cost of any storage accommodation provided especially for their use. SAMPLES The Contractor shall furnish at his own cost any samples of materials or workmanship including concrete test cubes required for the works that may be called for by the PROJECT MANAGER for his approval until such samples are approved by the PROJECT MANAGER and the PROJECT MANAGER, may reject any materials or workmanship not in his opinion to be up to approved samples. The PROJECT MANAGER shall arrange for the testing of such materials as he may at his discretion deem desirable, but the testing shall be made at the expense of the Contractor and not at the expense of the PROJECT MANAGER. The Contractor shall pay for the testing in accordance with the current scale of testing charges laid down by the Ministry of Roads, Housing and Public Works. The procedure for submitting samples of materials for testing and the method of marking for identification shall be as laid down by the PROJECT MANAGER The Contractor shall allow in his tender for such samples and tests except those in connection with nominated sub-contractors' work. GOVERNMENT ACTS REGARDING WORKPEOPLE ETC. Allow for complying with all Government Acts, Orders and Regulations in connection with the employment of Labour and other matters related to the execution of the works. In particular the Contractor's attention is drawn to the provisions of the Factory Act 1950 and his tender must include for all costs arising or resulting from compliance with any Act, Order or Regulation relating to Insurances, pensions and holidays for workpeople or so the safety, health and welfare of the workpeople. The Contractor must make himself fully acquainted with current Acts and Regulations, including Police Regulations regarding the movement, housing, security and control of labour, labour camps , passes for transport, etc. It is most important that the Contractor, before tendering, shall obtain from the relevant Authority the fullest information regarding all such regulations and/or restrictions which may affect the organisation of the works, supply and control of labour, etc., and allow accordingly in his tender. No claim in respect of want of knowledge in this connection will be entertained.	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	
A	SECURITY OF WORKS ETC. The Contractor shall be entirely responsible for the security of all the works stores, materials, plant, personnel, etc., both his own and sub-contractors' and must provide all necessary watching, lighting and other precautions as necessary to ensure security against theft, loss or damage and the protection of the public.	
B	PUBLIC AND PRIVATE ROADS. Maintain as required throughout the execution of the works and make good any damage to public or private roads arising from or consequent upon the execution of the works to the satisfaction of the local and other competent authority and the PROJECT MANAGER	
C	EXISTING PROPERTY. The Contractor shall take every precaution to avoid damage to all existing property including roads, cables, drains and other services and he will be held responsible for and shall make good all such damage arising from the execution of this contract at his own expense to the satisfaction of the PROJECT MANAGER	
D	VISIT SITE AND EXAMINE DRAWINGS. The Contractor is recommended to examine the drawings and visit the site the location of which is described in the Particular Preliminaries hereof. He shall be deemed to have acquainted himself therewith as to its nature, position, means of access or any other matter which, may affect his tender. No claim arising from his failure to comply with this recommendation will be considered.	
E	ACCESS TO SITE AND TEMPORARY ROADS. Means of access to the Site shall be agreed with the PROJECT MANAGER prior to commencement of the work and Contractor must allow for building any necessary temporary access roads for the transport of the materials, plant and workmen as may be required for the complete execution of the works including the provision of temporary culverts, crossings, bridges, or any other means of gaining access to the Site. Upon completion of the works, the Contractor shall remove such temporary access roads; temporary culverts, bridges, etc., and make good and reinstate all works and surfaces disturbed to the satisfaction of the PROJECT MANAGER The Contractor should also allow for relocating existing fence (approx. 30 metres long).	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	
A	AREA TO BE OCCUPIED BY THE CONTRACTOR The area of the site which may be occupied by the Contractor for use of storage and for the purpose of erecting workshops, etc., shall be defined on site by the PROJECT MANAGER	
B	OFFICE ETC. FOR THE PROJECT MANAGER (NOT APPLICABLE) The Contractor shall provide, erect and maintain where directed on site and afterwards dismantle the site office of the standard type, complete with furniture. He shall also provide a strong metal trunk complete with strong hasp and staple fastening and two keys. He shall provide, erect and maintain a lock-up type water or bucket closet for the sole use of the PROJECT MANAGER including making temporary connections to the drain where applicable to the satisfaction of Government and Medical Officer of Health and shall provide services of cleaner and pay all conservancy charges and keep both office and closet in a clean and sanitary condition from commencement to the completion of the works and dismantle and make good disturbed surfaces. The office and closet shall be completed before the Contractor is permitted to commence the works. The Contractor shall make available on the Site as and when required by the "PROJECT MANAGER" a modern and accurate level together with levelling staff, ranging rods and 50 metre metallic or linen tape.	
C	WATER AND ELECTRICITY SUPPLY FOR THE WORKS The Contractor shall provide at his own risk and cost all necessary water, electric light and power required for use in the works. The Contractor must make his own arrangements for connection to the nearest suitable water main and for metering the water used. He must also provide temporary tanks and meters as required at his own cost and clear away when no longer required and make good on completion to the entire satisfaction of the PROJECT MANAGER . The Contractor shall pay all charges in connection herewith. No guarantee is given or implied that sufficient water will be available from mains and the Contractor must make his own arrangements for augmenting this supply at his own cost. Nominated Sub--contractors are to be made liable for the cost of any water or electric current used and for any installation provided especially for their own use.	
D	SANITATION OF THE WORKS The Sanitation of the works shall be arranged and maintained by the Contractor to the satisfaction of the Government and/or Local Authorities, Labour Department and the PROJECT MANAGER	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	
A B C D C.	SUPERVISION AND WORKING HOURS The works shall be executed under the direction and to the entire satisfaction in all respects of the PROJECT MANAGER who shall at all times during normal working hours have access to the works and to the yards and workshops of the Contractor and sub-Contractors or other places where work is being prepared for the contract. PROVISIONAL SUMS. The term "Provisional Sum" wherever used in these Bills of Quantities shall have the meaning stated in Section A item A7(i) of the Standard Method of Measurement. Such sums are net and no addition shall be made to them for PRIME COST (OR P.C.) SUMS. The term "Prime Cost Sum" or "P.C. Sum" wherever used in these Bills of Quantities shall have the meaning stated in Section A item A7 (ii) of the Standard Method of Measurement. Persons or firms nominated by the PROJECT MANAGER to execute work or to provide and fix materials or goods are described herein as Nominated Sub-Contractors. Persons or firms so nominated to supply goods or materials are described herein as Nominated Suppliers. PROGRESS CHART. The Contractor shall provide within two weeks of Possession of Site and in agreement with the PROJECT MANAGER a Progress Chart for the whole of the works including the works of Nominated Sub-Contractors ; one copy to be handed to the PROJECT MANAGER and a further copy to be retained on Site. Progress to be recorded and chart to be amended as necessary as the work proceeds. ADJUSTMENT OF P.C. SUMS. In the final account all P.C. Sums shall be deducted and the amount properly expended upon the PROJECT MANAGER'S order in respect of each of them added to the Contract sum. The Contractor shall produce to the PROJECT MANAGER such quotations, invoices or bills, properly receipted, as may be necessary to show the actual details of the sums paid by the Contractor. Items of profit upon P.C. Sums shall be adjusted in the final account pro-rata to the amount paid. Items of "attendance"	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	
A	ADJUSTMENT OF P.C. SUMS. Ctd..... Should the Contractor be permitted to tender and his tender be accepted of any work for which a P.C. Sum is included in these Bill of Quantities profit and attendance will be allowed at the same rate as it would be if the work were executed by a Nominated Sub-Contractor. B ADJUSTMENT OF PROVISIONAL SUMS. In the final account all Provisional Sums shall be deducted and the value of the work properly executed in respect of them upon the PROJECT MANAGER's order added to the Contract Sum. Such work shall be valued as described for Variations, but should any part of the work be executed by a Nominated Sub-Contractor, the value of such work or articles for the work to be supplied by a Nominated Supplier, the value of such work or articles shall be treated as a P.C. Sum and profit and attendance comparable to that contained in the priced Bills of Quantities for similar items added. C NOMINATED SUB-CONTRACTORS When any work is ordered by the PROJECT MANAGER to be executed by nominated sub-contractors, the Contractor shall enter into sub-contracts and shall thereafter be responsible for such sub-contractors in every respect. Unless otherwise described the Contractor is to provide for such Sub-Contractors any or all of the facilities described in these Preliminaries. The Contractor should price for these with the nominated Sub-contract Contractor's work concerned in the P.C. Sums under the description "add for Attendance". D DIRECT CONTRACTS Notwithstanding the foregoing conditions, the Government reserves the right to place a "Direct Contract" for any goods or services required in the works which are covered by a P.C. Sum in the Bills of Quantities and to pay for the same direct. In any such instances, profit relative to the P.C. Sum the priced Bills of Quantities will be adjusted as described for P.C. Sums and allowed.	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	
A B C D	ATTENDANCE UPON OTHER TRADESMEN, ETC. The Contractor shall allow for the attendance of trade upon trade and shall afford any tradesmen or other persons employed for the execution of any work not included in this Contract every facility for carrying out their work and also for use of his ordinary scaffolding. The Contractor, however, shall not be required to erect any special scaffolding for them. The Contractor shall perform such cutting away for and making good after the work of such tradesmen or persons as may be ordered by the PROJECT MANAGER and the work will be measured and paid for to the extent executed at rates provided in these Bills. INSURANCE The Contractor shall insure as required in Clause 30 of the Conditions of Contract. No payment on account of the work executed will be made to the Contractor until he has satisfied the PROJECT MANAGER either by production of an Insurance Policy or and Insurance Certificate that the provision of the foregoing Insurance Clauses have been complied with in all respects. Thereafter the PROJECT MANAGER shall from time to time ascertain that premiums are duly paid up by the Contractor who shall if called upon to do so, produce the receipted premium renewals for the PROJECT MANAGER's inspection. PROVISIONAL WORK All work described as "Provisional" in these Bills of Quantities is subject to remeasurement in order to ascertain the actual quantity executed for which payment will be made. All "Provisional" and other work liable to adjustment under this Contract shall left uncovered for a reasonable time to allow all measurements needed for such adjustment to be taken by the PROJECT MANAGER Immediately the work is ready for measuring, the Contractor shall give notice to the PROJECT MANAGER. If the Contractor makes default in these respects he shall if the PROJECT MANAGER so directs uncover the work to enable all measurements to be taken and afterwards reinstate at his own expense. ALTERATIONS TO BILLS, PRICING, ETC. Any unauthorised alteration or qualification made to the text of the Bills of Quantities may cause the Tender to be disqualified and will in any case be ignored. The Contractor shall be deemed to have made allowance in his prices generally to cover any items against which no price has been inserted in the priced Bills of Quantities. All items of measured work shall be priced in detail and the Tenders containing Lump Sums to cover trades or groups of work must be broken down to show the price of each item before they will be accepted.	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	
A	BLASTING OPERATIONS Blasting will only be allowed with the express permission of the PROJECT MANAGER in writing. All blasting operations shall be carried out at the Contractor's sole risk and cost in accordance with any Government regulations in force for the time being, and any special regulations laid down by the PROJECT MANAGER governing the use and storage of explosives. B MATERIALS ARISING FROM EXCAVATIONS Materials of any kind obtained from the excavations shall be the property of the Government. Unless the PROJECT MANAGER directs otherwise such materials shall be dealt with as provided in the Contract. Such materials shall only be used in the works, in substitution of materials which the Contractor would otherwise have had to supply with the written permission of the PROJECT MANAGER. Should such permission be given, the Contractor shall make due allowance for the value of the materials so used at a price to be agreed. C PROTECTION OF THE WORKS. Provide protection of the whole of the works contained in the Bills of Quantities, including casing , casing up, covering or such other means as may be necessary to avoid damage to the satisfaction of the PROJECT MANAGER and remove such protection when no longer required and make good any damage which may nevertheless have been done at completion free of cost to the Government. D REMOVAL OF RUBBISH ETC. Removal of rubbish and debris from the Buildings and site as it accumulates and at the completion of the works and remove all plant, scaffolding and unused materials at completion. E WORKS TO BE DELIVERED UP CLEAN Clean and flush all gutters, rainwater and waste pipes, manholes and drains, wash (except where such treatment might cause damage) and clean all floors, sanitary fittings, glass inside and outside and any other parts of the works and remove all marks, blemishes, stains and defects from joinery, fittings and decorated surfaces generally, polish door furniture and bright parts of metalwork and leave the whole of the buildings watertight, clean, perfect and fit for occupation to the approval of the PROJECT MANAGER	
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	
A. GENERAL SPECIFICATION. For the full description of materials and workmanship, method of execution of the work and notes for pricing, the Contractor is referred to the Ministry of Roads, Public Works and Housing General Specification dated 1976 or any subsequent revision thereof which is issued as a separate document, and which shall be allowed in all respects unless it conflicts with the General Preliminaries, Trade Preambles or other items in these Bills of Quantities. B. TRAINING LEVY The Contractor's attention is drawn to legal notice No. 237 of October, 1971, which requires payment by the Contractor of a Training Levy at the rate of 1/4 % of the Contract sum on all contracts of more than Kshs. 50,000.00 in value. C. MATERIALS ON SITE All materials for incorporation in the works must be stored on or adjacent to the site before payment is effected unless specifically exempted by the PROJECT MANAGER. This includes the materials of the Main Contractor, Nominated Sub-Contractors and Nominated Suppliers. D. HOARDING The Contractor shall enclose all the site under construction with a hoarding 2400 mm high consisting of iron sheets gauge 30 on 100 x 50 mm 2nd grade treated sawn cypress timber posts firmly secured at 1800 mm centres with two 75 x 50 mm 2nd grade treated sawn cypress timber rails. The Contractor is in addition required to take all precautions necessary for the safe custody of the works, materials, plant, public and Employer's property on the site. E. CONTRACTOR'S SUPERINTENDENCE/SITE AGENT The Contractor shall constantly keep on the works a literate English speaking Agent or Representative, competent and experienced in the kind of work involved who shall give his whole experience in the kind of work involved and shall give his whole time to the superintendence of the works. Such Agent or Representative shall receive on behalf of the Contractor all directions and instructions from the Project Manager and such directions shall be deemed to have been given to the Contractor in accordance with the Conditions of Contract.		
	<i>Carried to collection</i>	

ITEM	DESCRIPTION	
	<u>COLLECTION</u> Brought Forward From Page GP/ 1 Brought Forward From Page GP/ 2 Brought Forward From Page GP/ 3 Brought Forward From Page GP/ 4 Brought Forward From Page GP/ 5 Brought Forward From Page GP/ 6 Brought Forward From Page GP/ 7 Brought Forward From Page GP/ 8 Brought Forward From Page GP/ 9 Brought Forward From Page GP/ 10 Brought Forward From Page GP/ 11 Brought Forward From Page GP/ 12	
	TOTAL FOR GENERAL PRELIMINARIES CARRIED TO SUMMARY OF PRELIMINARIES	

MEASURED WORK

[illegible]

PROPOSED OFFICE RE-DESIGN OF EXISTING OFFICE SPACE INCLUDING PARTITIONING AND REFURBISHMENT WORKS AT GROUND AND 1ST FLOOR, EMBANKMENT PLAZA - NAIROBI

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	<u>NEW WORKS</u>				
	<u>PARTITIONS</u>				
	<u>Gypsum Wall Partitions</u>				
A	Supply, assemble and fix gypsum board partitions in panels consisting of steel studs at 600mm centers both ways with syrofoam infill; rawl bolted onto concrete floors, infilled with 12.5mm thick gypsum boards on both sides and 6mm thick glazing and permanent louvre ventilation; all including appropriate fixing brackets and all other accessories; all in accordance with the manufacturer's recommendation; as per the Project Architect's details	158	sm		
B	Prepare and apply one undercoat and two finishing coats of first quality silk vinyl plastic emulsion paint; to plastered wall surfaces; internal	316	sm		
	<u>Aluminium Partitions</u>				
	<u>The following in partitions comprising 18mm thick Laminated Medium Density Fibre board (MDF) in alumium framing and glazing approximately 2400mm from finished floor level;</u>				
C	100x45x2mm anodised powder coated aluminum framing to match existing fabricated to specification; horizontally	145	lm		
D E	Ditto but Vertically	176	lm		
F	20x15mm powder coated alumium beadings	140	lm		
G	Extra Over; 20mm Thick rubber strip to approval (Provisional)	155	lm		
	18mm thick laminated MDF Board on either side of aluminium framing (m.s)	32	sm		
H	<u>Glazing</u>				
	6mm Thick clear glass fixed to metal with aluminium connectors and rubber strips; panes exceeding 0.5 square meters but not exceeding 1.0 square meters	48	sm		
I	<u>Films</u>				
	Supply and fix one-way stripped films (as per sample on site) to ditto as directed	48	sm		
	<i>Carried to Collection</i>				

PROPOSED OFFICE RE-DESIGN OF EXISTING OFFICE SPACE INCLUDING PARTITIONING AND REFURBISHMENT
WORKS AT GROUND AND 1ST FLOOR, EMBANKMENT PLAZA - NAIROBI

[illegible]

PROPOSED OFFICE RE-DESIGN OF EXISTING OFFICE SPACE INCLUDING PARTITIONING AND REFURBISHMENT WORKS AT GROUND AND 1ST FLOOR, EMBANKMENT PLAZA - NAIROBI

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	<u>FLOOR FINISHES</u>				
	<u>Insitu Finishings</u>				
	<u>Approved tiles; premium quality; non slip Granito floor tiles to regular or other approved pattern; bedding and jointing in cement sand (1:4) mortar; grouting with matching cement to:-</u>				
A B	10mm thick to Floors level; internal	420	sm		
	Skirtings; 100mm wide with rounded junction with wall finish and coved junction with floor finish	88	lm		
	<u>Beds or Backings</u>				
C	<u>Screed; cement and sand (1:3)</u>				
	30mm thick one coat backings; wood floated to receive granito floor tiles (m/s) to concrete or blockwork base; to floors level; internal	420	sm		
D	<u>Suspended Acoustic Ceiling</u>				
	Replace worn out 600 x 600mm "Hunter-Douglas" Suspended miniaboard Accoustic ceiling panels; to match existing; including all the necessary aluminium suspended framing and branderings, panels suspension hangers, flush jointing and trap doors	84	sm		
E	<u>Heavy Duty Executive Window Blinds</u>				
	Supply and fix high quality executive window blinds; slate blinds each size 125mm wide x 210mm Thick; including all fixing accessories; to general glazed window surfaces; as per samples approved by the Project Architect	176	sm		
	<i>Carried to Collection</i>				

PROPOSED OFFICE RE-DESIGN OF EXISTING OFFICE SPACE INCLUDING PARTITIONING AND REFURBISHMENT
WORKS AT GROUND AND 1ST FLOOR, EMBANKMENT PLAZA - NAIROBI

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
A	<u>DOORS</u> <u>Aluminium Framed glass door</u> <u>Supply and fix the following purpose made powder coated aluminium framed glass door consisting 80 x 45 mm aluminium frames; with 6 mm thick glass to architect's details; including 100 mm brass butt hinges; 5 lever mortice lock; handles; overhead heavy duty door closers; stops and escuthion; all other iron mongery and fixing to frames; all to manufacturers specification</u> Overall Door size 900 x 2400 mm high	12	no		
	<i>Carried to Collection</i>				

PROPOSED OFFICE RE-DESIGN OF EXISTING OFFICE SPACE INCLUDING PARTITIONING AND REFURBISHMENT
WORKS AT GROUND AND 1ST FLOOR, EMBANKMENT PLAZA - NAIROBI

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	<u>COLLECTION</u> From page MW / 1 From pege MW / 2 From page MW / 3 From page MW / 4 From page MW / 5				
	TOTAL FOR MEASURED WORKS CARRIED TO GRAND SUMMARY				

ELECTRICAL INSTALLATION WORKS

ELECTRICAL INSTALLATION WORKS

PROPOSED OFFICE REORGANIZATION ON 1st FLOOR, EMBARKMENT PLAZA KENTRADE

BILL NO. E-1

ITEM No	ITEM DESCRIPTION	UNIT	QTY	UNIT RATE	AMOUNT KSHS	CTS
	Supply, install, test and commission the following complete as specified herein or approved equivalent:					
1.00	LIGHTING POINTS					
1.01	Lighting point wired in 3x1.5 mm ² PVC / SC CU Cables drawn in concealed 25 mm- Ø concealed HG PVC Conduits, complete with all accessories but excluding switches for:					
	a) One way switching	No	26			
	b) Two way switching	No	2			
	c) Intermediate switching	No	72			
2.00	LIGHTING SWITCHES					
2.01	10A, moulded ivory white flash switch plates as MK range as follows:					
	(a) One gang one way. [As MK]					
	(b) One gang two way. [As MK]	No	12			
	(c) Two gang two way. [As MK]	No	4			
	(d) Two gang one way. [As MK]	No	1			
	(e) Three gang one way. [As MK]	No	1			
	(f) One gang intermediate. [As MK]	No	1			
		No	2			
3.00	LIGHTING FITTINGS					
3.01	lighting fittings complete with all accessories:					
	a) 36 w 1200mm single batten LED luminaire with clear prismatic diffusers as CAT No CO2100Z4K.	No	2			
	b) LED modular recessed in door 14/19 watt 240 vac fitting [As Linn] to approval CAT No CU1000Z3K.	No	26			
	c) Surface modular luminaire LED for 4 x 14 watts glare Protech /anti-sparking prismatic optic as OMEGA to approval CAT No OMPM3400Z4K.	No	72			
SUB TOTAL FOR BQ/E-1 CARRIED FORWARD TO COLLECTION PAGE						

BQ/ E – 1

PROPOSED OFFICE REORGANIZATION ON 1st FLOOR, EMBARKMENT PLAZA KENTRADE

ITEM No	ITEM DESCRIPTION	UNIT	QTY	UNIT RATE	AMOUNT KSHS	CTS
	Supply, install, test and commission the following complete as specified herein or approved equivalent:					
4.00	SUB MAINS WIRING POWER SUPPLY					
4.01	6 mm ² CU/PVC/SWA/PVC 2 core (ref.6944X) armoured power supply cable complete with accessories.	M	85			
5.00	TRUNKING AND DUCTING					
5.01	Lay Metal clad cable tray 150mm width complete with accessories in the electrical service duct to each floor for internal power reticulation.	M	75			
5.02	Lay HG/PVC conduit of size 50mm Ø from the electrical service duct to the incoming point for the building.	M	35			
5.03	Lay flexible HG/PVC conduit of size 20mm Ø from the electrical service duct to various utilities (ie CCTV)	M	50			
5.04	Rectangular skirting trunking type 'B' of dimensions 150 mm width x 50 mm depth 3 compartment flush along all walls and or accessories as shall be instructed and approved by Electrical Engineer. (Trunking to be powder coated and white in colour / to match existing) complete with inside and outside corner bends, end covers, cover plates with outlet provisions for data/ voice and power points.	M	205			
6.00	RAW POWER POINTS					
6.01	Socket outlet point wired in 3 x 2.5 mm ² PVC/SC CU Cables drawn in concealed 25 mm Ø diameter HG PVC ring of Conduits / metal clad trunking, complete with all accessories but excluding plates. (Twin)		40			
6.02	13A, moulded ivory white switched socket outlet plates as MK or Crabtree as follows: Twin switched		40			
SUB TOTAL FOR BQ/E-2 CARRIED FORWARD TO COLLECTION PAGE						

BQ/ E – 2

PROPOSED OFFICE REORGANIZATION ON 1st FLOOR, EMBARKMENT PLAZA KENTRADE

ITEM No	ITEM DESCRIPTION	UNIT	QTY	UNIT RATE	AMOUNT KSHS	CTS
	Supply, install, test and commission the following complete as specified herein or approved equivalent:					
7.00	INTERNAL POWER DISTRIBUTION					
7.01	Cable termination / extension box as type No 2CVA 002 101 R1001.	No	4			
8.00	100 amps 12 way SPN wall mounted recessed and					
8.01	hinged flash cover consumers service unit complete with integral isolator and all other accessories except MCBs [as ABB] WING B	No	1			
8.02	Supply and install MCBs complete with all accessories:					
	(a) 10 amps single pole [As ABB]	No	4			
	(b) 20 amps single pole [As ABB]	No	4			
	(c) 32 amps single pole {As ABB}	No	1			
	(d) 63 amps single pole {As ABB}	No	1			
	(e) Spare blanking plate	No	2			
9.00	<u>DISCONNECTIONS AND REMOVAL WORKS</u>					
9.01	Carefully remove, store and arrange for handing over to client of existing or damaged and obsolete electrical cabling, lighting fittings, distribution boards / consumers service units and other electrical services fittings and or accessories as shall be instructed and approved by Electrical Engineer.	L.S	Item			
10.00	<u>TEMPORARY POWER SUPPLY</u>					
10.01	Allow for temporary connection of power	L.S	Item			
SUB TOTAL FOR BQ/E-3 CARRIED FORWARD TO COLLECTION PAGE						

BQ/ E- 3

PROPOSED OFFICE REORGANIZATION ON 1st FLOOR, EMBARKMENT PLAZA KENTRADE

ITEM No	ITEM DESCRIPTION	UNIT	QTY	UNIT RATE	AMOUNT KSHS	CTS
	Supply, install, test and commission the following complete as specified herein or approved equivalent:					
11.00	FIRE ALARM SYSTEM					
11.01	240 vac, 50 Hz electrical / electronic surface wall mounted 2 zone Fire alarm panel. (As Manvier). Works include but not limited to identification of interconnections terminals, cabling and programming with the following features : (i) Surface flush mounted (ii) Zone LEDs	Unit	1			
11.02	Fire alarm manual call point wired in 2core x 1.5 mm ² PVC/SC CU screened fire resistant Cables drawn in concealed 25 mm Ø diameter HG PVC ring of Conduits / metal clad trunking, complete with all accessories but excluding plates.	No	8			
11.03	Addressable manual call point to be installed recessed in building fabric (As Menvier)	No	8			
11.04	Addressable photoelectric smoke detector complete with common base (As Menvier)	No	16			
11.05	24v polarised 6" addressable wall mounted fire bell / sounder (As Menvier)	No	2			
12.00	UNITERRUPTIBLE POWER SUPPLY POINT					
12.01	240 vac 20 KVA surface mounted manual type manual power supply switch complete with accessories	No	1			
12.02	10 mm ² PVC / SC power supply cable complete with accessories	M	30			
SUB TOTAL FOR BQ/E-4CARRIED FORWARD TO COLLECTION PAGE						

BQ/E – 4

PROPOSED OFFICE REORGANIZATION ON 1st FLOOR, EMBARKMENT PLAZA KENTRADE

ITEM No	ITEM DESCRIPTION	UNIT	QTY	UNIT RATE	AMOUNT KSHS	CTS
	Supply, install, test and commission the following complete as specified herein or approved equivalent:					
13.01	Exit signage point wired in 3 x 1.5 mm ² single core PVC Cables drawn in concealed 20 mm diameter heavy gauge PVC Conduits, complete with all accessories.	No	6			
13.02	Supply and install the following 2.2 – 5 watts ultra slim aluminium bodied LED 3 hour duration maintained and viewing distance up to 23 m fire exit signs as follows: Blade suspended [As THORN CAT No VBLNMC]	No	6			
14.01	Electric hand drier point wired in 3 x 2.5 mm ² single core PVC Cables drawn in concealed 20 mm diameter heavy gauge PVC Conduits, complete with all accessories.	No	4			
14.02	Supply and install the following 240 vac wall mounted high pressure air hand drier	No	4			
15.01	Fan extractor point wired in 3 x 2.5 mm ² single core PVC Cables drawn in concealed 20 mm diameter heavy gauge PVC Conduits, complete with all accessories.	No	4			
15.02	Supply and install the following 0.2 watts 240 vac wall mounted automatic low noise extractor fan	No	4			
16.00	Carry out earthing on all the installation and bond all metallic pipe work.	L.S	Item			
17.00	Carry out all the electrical type tests on the electrical installation and ensure that the system complies fully with the I.E.E / Kenya Power & Lighting Co. Ltd Regulations	L.S	Item			
SUB TOTAL FOR BQ/E-5 CARRIED FORWARD TO COLLECTION PAGE						

BQ/E – 5

COLLECTION PAGE FOR ELECTRICAL INSTALLATION WORKS

PROPOSED OFFICE REORGANIZATION ON 1st FLOOR, EMBARKMENT PLAZA KENTRADE

S / No	BILL No	ITEM No	BQ No	TOTAL KSHS	CTS
1	E1	1.0 - 3.00	E – 1		
		4.00 – 6.00	E – 2		
		7.00 – 10.00	E - 3		
		11.00 – 12.00	E - 4		
		13.00 – 17.00	E – 5		
TOTAL (KSHS)					

GS – 1

STRUCTURED CABLING, DATA AND VOICE INSTALLATION WORKS

PROPOSED DATA AND NETWORK INSTALLATIONS AT 1ST FLOOR EMBANKMENT PLAZA FOR KENTRADE

READ THESE NOTES BEFORE FILLING THISBOQ

- 1. The items supplied MUST meet or surpass the outlined specifications. They must be the latest/current models in the market.**
- 2. The prices quoted shall be deemed to include all obligations under the contract/sub-contract including but not limited to supply of materials, devices (c/w necessary accessories and integration units), delivery to site, storage on site, installation, setting up, configuration, labour, testing, commissioning and necessary taxes.**

1ST FLOOR EMBANKMENT PLAZA, UPPER HILL

SCHEDULE 1:- DATA & VOICE NETWORK

Item	Description	Unit	Qty	Rate	Amount
1.01	Carefully remove, store and arrange for handing over to client of existing or damaged and obsolete data cabling, units and other fittings and or accessories as shall be instructed and approved by Electrical Engineer.	Item	Sum		
1.02	Clean and Reorgnise the exixting 42U Network Cabinet in the Data Centre as will be directed by the Project Electrical Engineer.	Item	Sum		
	Supply, install, set up, configure, test and commission the following Items as specified in ICT Works Section of this Tender Document.				
	Horizontal cabling:				
1.03	Four pair UTP CAT 6A cable as Siemons drawn in the existing trunkings to terminated at the patch panel and Dual RJ45 data outlets	LM	7930		
1.04	CAT 6A Dual RJ45 Data Outlets complete with face plates and RJ45 connectors as siemon or approved aquivalent	No.	89		
1.05	CAT 6A 48-port RJ 45 patch panels as Siemons or approved aquivalent	No.	4		
1.06	CAT 6A1U Rack Mount Cable Managers	No.	4		
	Sub-total C/F to Next Page				

Item	Description	Unit	Qty.	Rate	Amount
	Sub-total C/F from Previous Page				
1.07	CAT 6A 1 Metre,4 pair RJ45-RJ45 patch cords	No.	178		
1.08	CAT 6A 3 Metre,4 pair RJ45-RJ45 patch cords	No.	89		
1.09	1G SFP transceiver modules plus termination kit	No.	12		
1.10	8-core fiber optic cable (50/125) indoor	LM	100		
1.11	Fiber Optic Enclosure c/w Patch panel tray and adoptors.	No.	3		
1.12	1m Fiber Patch Cords	No.	12		
1.13	Pedestal trunking with provision for 4No. Data Outlet and 4No. Power s/o	No.	21		
1.14	2-Compartment Low Profile Floor Trunking	LM	63		
1.15	Factory fabricated Cable Tray 300m x 50mm c/w all applicable parts and accessorie	LM	70		
1.16	Workstaion Power points wired in 3x2.5mm2 sc/pvc insulated copper cables drawn in Floor Trunkingall their accessories but excluding socket outlets	No.	84		
1.17	13A, Single white moulded socket outlets as MK range	No.	84		
1.18	Relocate existing Network Cabinets and install (including necessary accessories) to positions to shown by the Project ICT Engineer	No.	1		
1.19	Install, terminate, configure and leave in working condition existing Network Switches and PBX (including necessary accessories)	No.	5		
	Sub-total C/F to Next Page				

Item	Description	Unit	Qty.	Rate	Amount
	Sub-total C/F from Previous Page				
	Distribution of Clean Power to Network Cabinets				
1.20	4-Way Consumer Unit c/w 50A (or closest) Isolator	No.	1		
1.21	25mm 3-Core Copper PVC Insulated and Sheathed Cable to connect the existing UPS and the above 4-Way Consumer Unit	LM	5		
1.22	15AMCB or closest	No.	1		
1.24	30A MCB or closest	No.	1		
1.24	15A Isolator or closest for the network Cabinet	No.	1		
1.25	30A Isolator or closest for the Network cabinet	No.	1		
1.26	16mm 3-Core Copper PVC Insulated and Sheathed Cable to connect the above 4-Way Consumer Unit and the Network Cabinet Isolators.	LM	100		
	Sub-total for Data & Voice Network C/F to Summary Page				

SCHEDULE 2:- ACCESS CONTROL NETWORK

Item	Description	Unit	Qty	Rate	Amount
	Supply, install, set up, configure, test and commission the following Items as specified in SECTION F of this Tender Document.				
2.01	Four pair UTP CAT 6A cable drawn in the existing trunkings with one end patched at Patch Panel and the other end connected to RJ45 port of the Access Control Module	LM	1,220		
2.02	CAT 6 48 port RJ 45 patch panel	No.	1		
2.03	CAT 6 1U Rack Mount Cable Managers	No.	1		
2.04	CAT 6 Factory manufactured 1Metre,4 pair RJ45-RJ45 patch cords	No	27		
2.05	Single Stand alone IP Based Access Control Module that supports multiple verification methods (face, fingerprint, card, password, combinations between them), Time and Attendance that is integratable to major Third Party ERP (e.g. Oracle/Netsuite, SAP, Microsoft, Info etc) c/w Exit Button, Emergency Break Break Glass, Maglock of 300Kg holding force, Brackets as ZL and any other necessary accessory as ZKTeco MB360 or approved equivalent of similar capability and quality or better	No.	27		
2.06	Web-Based Time and Attendance Management Software as ZKTeco BioTime 8.5 or approved equivalent of similar capability and quality or better to be installed in existing Server.	Item	Sum		
	Sub-total for Access Control C/F to Summary Page				

SCHEDULE 3:- TESTING & COMMISSIONING

Item	Description	Unit	Qty	Rate	Amount
3.01	Test all the Active Devices to ensure they are in optimum working order.				
3.02	Carry out Network Cable Test for Data & Access Control Networks with an Industry Standard Equipment and document th test results in three (3No.) Bounded Hard and two (2No.) Soft Copies in a Flash Disk.	No	205		
3.03	Supply to the Project ICT Engineer Network Documentation (entailing As-installed Drawings/ Schematics for Data & Access Control Networks and Clean Power Installation, Cable Test Results , Installation, Operation & Maintenace Manuals for Active Devices) all in three (3No.) copies of bound booklet or box file and two (2No.) soft copies in a Flash Disk.	Item	Sum		
	Sub-total for Testing & Commissioning C/F to Summary Page				

SUMMARY PAGE

ITEM	DESCRIPTION	AMOUNT (KSHS)
	<u>1ST FLOOR EMBANKMENT PLAZA, UPPER HILL</u>	
1	SCHEDULE 1:- DATA & VOICE NETWORK	
2	SCHEDULE 2: ACCESS CONTROL NETWORK	
3	SCHEDULE 3: TESTING & COMMISSIONING	
	TOTAL FOR DATA & NETWORK INSTALLATIONS CARRIED TO GRAND SUMMARY PAGE	

|

PROVISIONAL SUMS

PROPOSED OFFICE RE-DESIGN OF EXISTING OFFICE SPACE INCLUDING PARTITIONING AND
REFURBISHMENT WORKS AT GROUND AND 1ST FLOOR, EMBANKMENT PLAZA - NAIROBI

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	<u>PROVISIONAL SUMS</u> <u>The following provisional sums are to be measured on completion and priced in accordance with the rates contained in these bills of quantities or prorata thereto or deducted in whole if not required</u> A Allow a provisional sum of Kenya Shillings Five Hundred Thousand (Kshs 500,000.00) only for Contingencies		ITEM		
	TOTAL FOR PROVISIONAL SUMS CARRIED TO GRAND SUMMARY				

GRAND SUMMARY

PROPOSED OFFICE RE-DESIGN OF EXISTING OFFICE SPACE INCLUDING PARTITIONING AND REFURBISHMENT WORKS AT GROUND AND 1ST FLOOR, EMBANKMENT PLAZA - NAIROBI

GRAND SUMMARY

ITEM	DESCRIPTION	Page No.	FOR TENDERER USE ONLY	FOR OFFICIAL USE ONLY
			K.SHS.	K.SHS.
A	PARTICULAR PRELIMINARIES	PP / 8		
B	GENERAL PRELIMINARIES	GP / 13		
C	MEASURED WORKS	MW / 6		
D	ELECTRICAL INSTALLATION WORKS	GS - 1		
E	STRUCTURED CABLING, DATA AND VOICE INSTALLATION WORKS	H / 6		
F	PROVISIONAL SUMS	PS / 1		
	GRAND TOTAL (IN KSHS - INCLUSIVE OF VAT) CARRIED TO FORM OF TENDER			

Amount in words. Kenya Shillings

.....

.....

Tenderer's Signature and stamp

Address

..... Date

.....

Witness Signature

Address

..... Date

.....